



F.no-IIIT-D/Bldg Proj/Boundary Wall /263/2018

Dated : 06.11.2020

SPOT QUOTATION

Sealed item rate quotations are invited in two envelop system for the following work on behalf of the Registrar IIIT Delhi from Eligible Contractors for **Concertina Civil Works at IIITD Campus**, so as to reach the office of the undersigned upto 3PM on **12th Nov 2020** to be opened on the same day at 3:00 PM, in the office of the CE, A-203 2nd Floor of Academic Block, IIIT-D Campus, Okhla Phase-III New Delhi-110020 in presence of the intending bidders who so wish to attend.

EMD : Rs 4000/-(Four thousand only) in form of DD payable in favour of “**IIITD Collections**”

1. The works shall be carried out as per the relevant CPWD / BIS Standards and Terms and conditions, Specifications, BOQ and areas/locations as directed complete.
2. **Time Allowed:** 10 days from issue of work order.
3. Schedule of quantity: As per enclosed BOQ. To be filled in neat handwriting.
4. Clause 12 of GCC CPWD is applicable for EI/SI.
5. Contractor must visit site before quoting and fully satisfy himself of the site conditions.
6. Contractor must possess valid GST, PAN, and TIN no.
7. No T&P shall be issued to the Contractor. The contractor shall be provided with electricity and water at one point, he shall make his own arrangements for further distribution of electricity , water supply and all other labour, tools, plant and equipment etc as required for the works complete. Any damage done to existing walls /ceiling /floors /electrical /fire alarm/ fighting/plumbing equipment /building during execution shall be on the part of the Contractor.
8. **Eligibility Criteria:** The agencies must have satisfactory executed similar works in Govt Deptts/PSU/Reputed Pvt sector /MNCs a three works each of value of Rs 0.80 Lac or two works each of value 1.20 Lac or one work of value 1.60 Lac during last 5 years to submit the experience certificates for the works and registration certificates with Govt. Depts. if any. The said certificates along with the EMD be enclosed in **Envelope-A**. The applications not supported with requisite experience certificates shall not be entertained
9. The priced bill of quantities, all duly signed by the authorized signatory of the firms. This will be enclosed in **Envelope- II**.



10. Payment shall be made as per actual quantities of executed works against RA/Final bill at all locations as directed.
11. Security Deposit / Retention money shall be Five percent (5%) of the value of executed works and will be deducted from each and every payment made to the contractor against running account bill submitted for the work done at site.
12. Conditional offers will not be accepted. The offer shall remain valid for 30days.
13. Contractor should depute a qualified supervisor dedicated for this work, who will monitor and coordinate work from contractor's side and interact with the IIITD Engineers, responsible for supervision of work, on regular basis.
14. Rates to quoted are inclusive of all taxes, duties, cartage, loading unloading and shifting to location as called for.
15. Contractor will take due permission for entry of all his workers in IIITD. No unauthorized person will be allowed to work inside.
16. During execution of work, Engineer may make minor changes in the scope of work as per site conditions or other reasons. Contractor will have no extra claim in his rates for the same.
17. All standard protocols such as wearing masks, using sanitizer, maintaining safe distancing norms must be followed by the Contractor and his workers to prevent spread of coronavirus failing which expulsion/ penalty shall be levied on the agency.
18. The workers shall be scanned for temperature before entry as per norms and actions per policy taken.
19. All are supposed to use identified utilities of the Institute only.
20. IIIT-D reserves the right to accept or reject any tender in part or whole without assigning any reasons thereof.

CE

**BOQ for Concertina Civil Works**

S.no	Description	Unit	Qty	Rate	Amount
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	550		
2	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	RM	200		
3	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with.	cum	6		
	Cement mortar 1:6 (1 cement : 6 coarse sand)				
4	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing:				
	1:2:4 (1 Cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	cum	5		
5	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
	Two or more coats on new work	Sqm	50		
6	Removal of old concertina coil outside the campus.	L/s	1		
7	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge :				
7.1	In cement mortar	cum	15		
	Total Amount				
	GST @ ___%				
	Total Amount with GST				

In words (Rs)

(_____)